



ICAP

BOQ FOR CONSTRUCTION OF BOUNDRY WALL FOR ICAP DHA CITY PLOT

S.No.	Item	Description	Unit	Qty	Rate (Incl. All Tax)	Amount
1	EXCAVATION	Excavation 2 feet deep and 2 feet wide and 1230 feet long in rokey area as per site along the level of existing ground level complete in all respect.	cft	4,920		
2	BACK FILLING	Back filling with existing excavated soil after masonry of foundation on both sides with compaction complete in all respect.	cft	2,460		
3	LEAN CONCRETE	1:4:8 machine mix concrete under foundation of wall 24"x 6" x 1230' complete leveling and spreading	cft	1,230		
4	FOUNDATION MASONRY	foundation masonry 12" wide and 24" high up to foundation level laid with 1: 4 mix cement sand mortar using for block masonry complete with 3 day curing with water complete in all respect.	sft	2,460		
5	DPC	Dpc over foundation with 1:1 1/2 : 3 mix concrete 2" x 12"x 1230' complete with form work complex in plumb and level.	sft	1,230		
6	WALL MASONRY	Complete BOUNDRY WALL masonry with 6" thick blocks up to the height of 4' above ground level laid with 1: 4 mix cement sand mortar complete with pointing on both side of BOUNDRY wall with even finishing complete.	sft	4,305		
7	COLUMN MASNORY	masonry of columns 12"x 12" x4' making after each 10 feets of BOUNDRY WALL laid with 1:4 mix mortar complete with racking and pointing on all sides complete.	sft	430		
8	TOPING OF BOUNDRY WALL	On top of BOUNDRY wall 2" high coping with 1 :4 mix cement sand mortar plaster complete on top masonry of complete BOUNDRY wall	rft	1,360		

Authorized Signatory

COMPANY
SEAL